H.F. RESISTANCE AND SELF-CAPACITANCE OF SINGLE-LAYER SOLENOIDS*

By R. G. Medhurst, B.Sc.

(Communication from the Staff of the Research Laboratories of The General Electric Company, Limited, Wembley, England)

SUMMARY.—This paper contains the results of high-frequency resistance and self-capacitance measurements on about 40 coils, wound with copper wire on grooved Distrene formers. The measuring instrument was a twin-T impedance bridge.

For coils whose turns are widely spaced, the high-frequency resistance measurements are in good agreement with the theoretical values of S. Butterworth.[3] For closely-spaced coils, the measured values are very considerably below those of Butterworth.

A table of values of high-frequency resistance of coils having various values of length/diameter and spacing ratio is derived from these measurements.

It is shown that a good approximation to the high-frequency Q of coils of the type measured is given by the simple expression

$$Q = 0.15\ R\psi\sqrt{f}$$

where R is the mean radius (cm), f the frequency (c/s) and ψ depends on the length/diameter and the spacing ratios. A table of ψ has been calculated.

Measurements of self-capacitance were made with one end of the coils earthed. These measurements show a very considerable divergence from the formula of A. J. Palermo[14] though they are in quite good agreement with other previous experimental work. The self-capacitance of coils of this type is shown to be substantially independent of the spacing of the turns. It is given by an expression of the form

$$C_0 = HD \text{ picofarads}$$

where D (cm) is the mean coil diameter and H depends on the length/diameter.

A table of H is given, based on these measurements.

1. Introduction.

A GREAT deal of theoretical and experimental work has been published concerning the resistances of coils and their variation with frequency. The experimental work, in general, suffers both from its restricted application and from uncertainty as to the absolute error inherent in the method of measurement. The theoretical work, even where it is in reasonable agreement with experiment, tends to produce complicated formulae which lead to very considerable computation. Even now, after over a quarter of a century of work on every type of coil that has been used or proposed, the present writer knows of no reliable data from which Qs of even the simplest coils can be easily and quickly predicted.

The only comprehensive theory extant is that of S. Butterworth[1–5]. He gave formulae which purported to cover single-layer solenoids, wound with round wire, for any frequency, coil dimensions and spacing of turns. The only restriction was that the number of turns had to be large, the case of few turns only being dealt with when the length of the coil was small compared with its diameter, and the turns were not too closely spaced. He suggested modifications to include multi-layer coils and coils wound with stranded wire. All these formulae only dealt with copper losses, dielectric losses being assumed negligible. Dielectric loss must, if necessary, be allowed for separately.

This theoretical work has become so generally accepted that it is quoted as a basis for calculation in standard reference books (see, *e.g.*, ref. 12, pp. 78–80). It will be shown experimentally that Butterworth's theory is only applicable to coils having widely spaced turns (roughly $d/s < 0.5$). More closely spaced coils have a lower high-frequency resistance than that predicted by Butterworth, the discrepancy increasing as the coil length decreases relative to the diameter. For coils having $l/D = 1$, when $d/s = 0.6$ Butterworth's value is too high by 15 per cent, when $d/s = 0.7$ by 25 per cent, when $d/s = 0.8$ by 55 per cent and when $d/s = 0.9$ by 190 per cent.

During the determination of high-frequency resistance and inductance it was necessary to make allowance for the self-capacitance of the coils measured. It was

* MS accepted by the Editor, July, 1946

thought that self-capacitances calculated from the formula of A. J. Palermo[13] would be sufficiently accurate for this purpose. However, it was found that use of Palermo's formula led to variations, larger than the experimental error, of the apparent measured inductances over quite a small frequency range.

Measurements of self-capacitance of a wide range of single-layer coils were consequently carried out. The results failed to confirm Palermo's claim that the self-capacitance varies steeply with the spacing of turns. They are, instead, in quite good agreement with previous work, which had shown the self-capacitance to be very nearly independent of d/s. For coils having length/diameter = 1, Palermo's formula gives results which are greater than the measured value by 4 : 1 when $d/s = 0.9$, and smaller than the measured value by 1.6 : 1 when d/s = 0.1.

2. List of Symbols

D	represents mean diameter of coil	(cm)
R	represents mean radius of coil	(cm)
l	represents overall length of coil	(cm)
n	represents number of turns	
d	represents diameter of each wire	(cm)
s	represents distance between centres of adjacent turns	(cm)
d/s	represents spacing ratio of turns	
ρ	represents resistivity of wire	(ohm-cm)
f	represents frequency	(c/s)
τ	represents power factor of material of coil former	
C_0	represents self-capacitance of coil	(pF)
L_s	represents equivalent series inductance of coil	(μH)
R_s	represents equivalent series resistance of coil	(ohms)
f_0	represents self-resonant frequency of coil	(c/s)
ϕ	represents ratio of h.f. coil resistance to resistance at same frequency of same length of straight wire.	
ψ	is a function of l/D and d/s, occurring in the formula for Q,	

$$i.e.,\ Q = 0.15\, R\, \psi \sqrt{f}$$

Where $Q = 2\pi f L_s/R_s$.

$$z = \pi d \sqrt{\frac{2f}{10^9 \rho}} = \frac{1}{\sqrt{2}} \frac{\text{wire diameter}}{\text{current penetration depth}}$$

3.—Butterworth's Work on Single-Layer Solenoids

3.1. S. Butterworth's series of papers on solenoidal coils are based on two sets of formulae which he developed for single-layer solenoids. In both cases there is no restriction on the frequency. The first[1] apply to coils having any specified number of turns, the turns being "not too closely spaced," and the coils having lengths small compared with their diameters. The second[3] were evolved as a consequence of some measurements by C. N. Hickman, which were made on coils outside the range of conditions assumed in the formulae of Ref. 1, and consequently failed to agree with the results predicted by these formulae[2,7]. This second group of Butterworth formulae extended the theory to coils having arbitary spacing ratio, and arbitary ratio of length to diameter. The number of turns, however, had now to be assumed to be large. Butterworth's method of deriving his second group of formulae is as follows:




Fig. 1. *Views from above (a) and transverse to the wires (b) of Butterworth's infinite plane system of parallel wires.*

He took as his starting-point a system consisting of an infinite number of parallel wires of equal diameters, equally spaced and lying in the same plane as shown in Fig. 1, which shows a portion of the system seen from above and end-on. He set out to solve three problems, namely, to determine the losses in the system (*a*), when the wires carry equal alternating currents, i, flowing in the same direction; (*b*), when they are situated in a uniform alternating magnetic field H_1 parallel to the plane of the wires and perpendicular to their axes; and (*c*), when they are situated in a similar uniform field H_2 perpendicular to the plane of the wires. We shall call H_1 and H_2 the axial and transverse fields respectively.

Each of these problems involved the solution, by a method of successive approximations, of a set of an infinite number of linear equations, each containing an infinite number of variables. Butterworth's solutions are

contained in three tables, for a range of d/s from 0.1 to 1.0, in steps of 0.1 (*i.e.*, from widely separated turns to turns touching).

In order to apply these solutions to solenoidal coils, Butterworth worked out the field associated with the coil by adding to the field associated with an infinitely long solenoid a modifying field produced by its ends, considered as a circular disc of poles. This field was resolved into two components, one parallel to the axis of the coil (the axial field) and the other perpendicular to the axis (the transverse field), and the mean-square value of each over the length of the coil deduced.

Now, he pointed out that each short section of wire may, if the wire diameter is small compared with the coil diameter, be treated as part of a plane system, of the kind already considered. He considered that, as a sufficiently close approximation, the axial and transverse fields associated with the coil could be replaced by their mean-square values, these being considered to act uniformly along the length of the equivalent plane system, now taken as being infinitely long. Under such conditions, he showed that the total losses in the system equivalent to the coil could be obtained by summing the separate losses deduced from the solutions of his three problems.

His results for very high frequencies are summarized in a table which is reproduced here as Table I. The quantity tabulated is the ratio of the high-frequency resistance of a coil, assumed to have a large number of turns, to the resistance at the same frequency of a straight wire of the same length and diameter as the wire forming the coil. This straight-wire resistance can be calculated from a well-known formula. The variables of Table I are the ratio length/diameter of the coil, and the spacing ratio d/s.

" Very-high frequency " has to be defined in terms of the diameter and electrical constants of the wire. It is a frequency higher than that at which the current penetration depth is some arbitrary fraction, say, 1/10th, of the wire diameter. It is convenient to express the high-frequency resistance of a round wire in terms of a quantity z, which is defined by the relation

$$z = \pi d \sqrt{\frac{2f}{10^9 \rho}} = 0.107\, d \sqrt{f} \text{ for copper.}$$

Now, the current penetration depth in copper at frequency f

$$= \frac{1}{2\pi}\sqrt{\frac{10^9\rho}{f}}$$

Hence, it follows immediately that the criterion, given above, that the frequency should be " very high " may be written in the form

$$z > 10/\sqrt{2}$$

i.e., $z > 7$ approximately.

3.2. Certain curious features are apparent in this Butterworth table. Particularly surprising are the high values that appear when the turns are closely spaced. Suppose for example, that we take a coil having a length/diameter $= 0.4$ and spacing ratio $= 0.8$—that is to say, with turns quite close. If we bring the turns a little closer to give a spacing ratio of 0.9, the length/diameter ratio being thereby only slightly changed, we are to expect the h.f. resistance to increase in the ratio of about 2.7 to 1. This would be surprising. For a spacing ratio of 1.0 the value infinity appears in the table; *i.e.*, when the turns are brought very close the h.f. resistance becomes infinitely large.

TABLE I

$\frac{d}{s}$	Coil Length/Coil Diameter											
	0	0.2	0.4	0.6	0.8	1.0	2	4	6	8	10	∞
1.0	∞	∞	∞	∞	∞	∞	∞	∞	∞	∞	∞	3.41
0.9	18.2	17.5	16.1	14.6	13.2	11.9	8.02	5.27	4.39	3.96	3.78	3.11
0.8	6.49	6.32	5.96	5.57	5.23	4.89	3.91	3.20	3.04	2.97	2.92	2.82
0.7	3.59	3.53	3.43	3.29	3.17	3.07	2.74	2.61	2.51	2.51	2.50	2.52
0.6	2.36	2.35	2.32	2.29	2.26	2.23	2.16	2.15	2.14	2.16	2.16	2.22
0.5	1.73	1.74	1.75	1.75	1.75	1.76	1.77	1.85	1.85	1.86	1.86	1.93
0.4	1.38	1.39	1.41	1.42	1.44	1.45	1.49	1.56	1.57	1.59	1.60	1.65
0.3	1.16	1.19	1.21	1.22	1.22	1.24	1.28	1.34	1.34	1.35	1.36	1.39
0.2	1.07	1.08	1.08	1.10	1.10	1.10	1.13	1.16	1.16	1.17	1.17	1.19
0.1	1.02	1.02	1.03	1.03	1.03	1.03	1.04	1.04	1.04	1.04	1.04	1.05

Butterworth's theoretical values of the ratio of the h.f. coil resistance to the resistance at the same frequency of the same length of straight wire.

However, although this infinite value of the h.f. resistance holds for coils whose length varies from zero to a value indefinitely large, when the length actually becomes infinite there is a discontinuity, the h.f. resistance assuming a value 3.41 times the straight-wire resistance.

It will be useful to consider where, in Butterworth's calculation, these unexpectedly high values of h.f. resistance arise.

We have said that Butterworth evaluates separately three sets of losses, which he subsequently combines. These are (1) the losses due to the current in the wire under consideration and the currents in adjacent wires, (2) the losses due to the axial field (H_1 in Fig. 1) and (3) the losses due to the transverse field (H_2). Losses (1) and (2) show no surprising behaviour when the wires are closely spaced; the abrupt rise in h.f. resistance for close spacing is all due to loss (3). Butterworth tabulates a quantity g, varying with d/s, which when multiplied by $(d/s)^2$ and a factor depending on the length/diameter ratio of the coil, gives the contribution of the transverse field losses to the total losses. This is reproduced as Table II.

Table II gives values, worked out by Butterworth, of the ratio of the losses in one wire of his infinite parallel-wire system, acted on by a transverse field, to those in an isolated wire acted on by the same field. The table shows the variation of this quantity with the spacing ratio. If we work through the theory again, taking account only of the two adjacent wires (besides the wire in question), we find for a spacing ratio of 1.0 that g comes out as 3.40 instead of ∞. Values of g for wider spacings will now lie between 3.40 and 1. Consequently, it is the more remote wires that, for close spacings, make the largest contribution to Butterworth's values of g given in Table II. In the case of a coil, the transverse field will be concentrated near the ends of the coil, that is to say, it will be effective over the last few turns. Consequently, the contribution of the effect of the transverse field to the total coil losses would be expected to be of the order of the value of g that we have just worked out, rather than of that given by Butterworth.

So far, we have only considered the results given by Butterworth for "very high frequency." We shall see later (Section 14) that it is also necessary to proceed with caution when trying to make use of his low-frequency results.

TABLE II

d/s	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0
g	1.017	1.069	1.166	1.326	1.585	2.03	2.87	4.83	12.5	∞

That part of the resistance due to the transverse field rises steeply for spacing ratios over 0.7, becoming infinite for $d/s = 1.0$. In this latter case, the parallel-wire system becomes a continuous infinite metal screen at right angles to the field.

We can show, qualitatively, that Butterworth's high h.f. resistance values, for coils having closely-spaced turns, may be expected to be absent in practice. Butterworth has substituted for the actual transverse field of a coil a uniform field whose square is the mean-square value—obtained by a method of approximate integration—of the transverse field. This uniform field is supposed to be imposed on a system consisting of an infinite number of parallel wires, and we have to consider the effect on any one wire of this field as modified by the eddy-currents set up in that wire and in all other wires of the system. Now, we shall show that the high losses predicted by Butterworth in each wire of this system are due chiefly to the presence of the more remote wires.

4. Previous Experimental Work on the A.C. Resistance of Single-layer Solenoids

Butterworth, in his second paper[3], compares his theoretical values of the a.c. resistances of single-layer solenoids with two sets of experimental results, those of C. N. Hickman[7] and G. W. O. Howe.[6]

C. N. Hickman used coils wound with very thick wire (0.518 cm diameter), each coil being 96 cm in length, the ratio of length/diameter varying from 3 to 17. He used a d/s value of 0.86. He employed a bridge method of measurement, at frequencies of 1, 2 and 3 kc/s. The coils were wound on "well-seasoned wooden cylinders." Comparison of Butterworth's predicted values of resistance and Hickman's measured values shows that the former are from 2 to 13 per cent higher than the experimental.

G. W. O. Howe, using a thermal method, measured coil resistances at radio frequencies. He gave results for two coils, each having a length/diameter ratio of about 10, wound with wire of diameters 0.163 cm and 0.264 cm respectively. The respective values of d/s were 0.49 and 0.90. The results for the widely-spaced coil are close to those predicted by Butterworth. Those for the closely-spaced coil are lower than the theoretical values by $5\frac{1}{2}$ per cent at the low-frequency end of Howe's frequency range, and 20 per cent at the high-frequency end. Howe made his measurements on long coils because, at that time, no satisfactory formulae had been suggested for short coils. He pointed out that short coils, such as occur almost invariably in practice, would be expected to give results considerably different from those predicted by the long-coil theory, and he suggested a tentative modification of this theory to make it applicable to short coils.

Not a great deal of additional experimental work has been published, since the publication of Butterworth's papers. The most important is that of Dr. Willis Jackson.[8] He pointed out that Butterworth's formulae had not hitherto been satisfactorily verified. The two principal difficulties that he mentioned were that " precision uses of bridge networks are not available at radio frequencies," and that the losses in a tuning capacitor, which can at radio frequencies be comparable with those of the coil being measured, could not usually be measured separately. He avoided these difficulties by using an ingenious method suggested by E. B. Moullin, involving measurements on a number of coils having the same dimensions but wound with wire of different metals. The method is elaborate, and it would not be practicable to use it for measuring more than a small number of coils. It constitutes a check on an existing theory, rather than a method of making absolute measurements, and in addition Jackson found that it did not give results sufficiently accurate to allow more than tentative conclusions to be drawn. He worked at about 1 Mc/s, his coils having a spacing ratio of 0.63.

Sets of Q-meter readings, corresponding to coils of various dimensions, have been published from time to time. Typical of these are the values quoted in an article by Art H. Meyerson.[9] Results are given from 25 to 60 Mc/s in the form of a table, and some very irregular curves are based on the measurements. These results seem characteristic of the Q-meter rather than of the coils.

Of the methods of measurement so far considered, only the thermal method of Howe seems likely to give reliable results. The objection to Howe's method is the practical one of the length of time required for each measurement.

5. Description of Coils used in the Present Series of Measurements

The intention of the present series of measurements was to provide an empirical substitute for Butterworth's theoretical h.f. resistance table (Table I). We shall see that the conditions that need to be fulfilled before Butterworth's table becomes applicable—i.e., that z should be high and the number of turns large (see below)—tend to become incompatible over part of the range of the table, more especially in the bottom left-hand region. That is to say, practically useful coils cannot be wound such that they work at a large z value, have a large number of turns, have a wide turn spacing and have a small length/diameter. To cover this region, some compromise had to be made, and the results are of theoretical rather than practical interest. Butterworth, constructing his table exclusively from theoretical formulae, did not encounter this difficulty. However, most high-frequency single-layer coils actually used do fall within the region covered by the body of the table, which is the practically important region.

It is specified in Butterworth's table that the number of turns shall be large, though there is no indication of the effect on the h.f. resistance of employing a finite number of turns. We can form a very rough estimate of the order of magnitude of this effect as follows. If we assume that the part of the losses in each wire due to proximity effect is to be attributed largely to the two immediately adjoining wires, one on each side, the effect of using a finite number of wires will be, principally, to diminish the proximity effect in two turns, those at each end of the coil. As a first approximation, the proximity effect in each of these end turns will be diminished by half, since there is only one wire adjacent to each. Thus the total proximity effect losses will be diminished by $2 \times \frac{1}{2} \times \frac{100}{n}$ %; i.e., by $\frac{100}{n}$ %.

Since, in practice, the proximity effect on each turn of more remote turns is not negligible, this expression will be too low. Since, however, proximity losses form only part of the total losses, this expression should give the order of magnitude of the effect of using a finite number of turns. It is not in violent disagreement with Butterworth's figures for very short coils, of not too close spacing, having a finite number of turns.

From this consideration, it was decided that the minimum number of turns that would be used was 30. In practice, the number of turns ranged from 30 for the smallest length/diameter coils to 50 for the largest.

The condition that the number of turns shall be large may, over part of Butterworth's table, be difficult to reconcile with the condition that the frequency shall be high, or, more correctly, that z should be large. From the expression for z, i.e.,

$$z = 0.107\, d\sqrt{f}$$

it is evident that both the wire diameter and the frequency must be as large as possible. As regards the frequency, since as we shall see later, we shall want to make use of a large tuning capacitance, in order to work at a high enough frequency our coil inductance must be as low as possible. That is to say, we must use the smallest permissible coil diameter and the smallest number of turns. The minimum number of turns has already been decided. As for the coil diameter, since the number of turns has a lower limit, and the spacing of turns and the ratio of coil length to coil diameter are determined by the position of the coil in Table I, we can only decrease the coil diameter by decreasing the diameter of wire. But it is evident from the form of the expression for z, that, for satisfying the " high-frequency " criterion, a large d is more important than a large f.

Specifically, since for a given number of turns and a given spacing ratio, the length of coil, l, is proportional to the diameter of wire, d, then the coil diameter D, for a given l/D ratio, will also be proportional to d. But f is proportional to $1/\sqrt{L}$, i.e., to $1/\sqrt{D}$, and hence to $1/\sqrt{d}$. So $\sqrt{f}$ is proportional to $1/(d)^{\frac{1}{2}}$, and hence z is proportional to $(d)^{\frac{3}{4}}$.

It is apparent that the upper limit to d is determined by the maximum permissible coil diameter. In the present work, the largest formers used had a diameter of $2\frac{1}{2}$in. This involved the use of wires of 18 and 20 S.W.G. for most of the coils. Furthermore, since for a given maximum coil diameter, the upper limit of z becomes increasingly severely diminished with decreasing value of length/diameter, no coils were constructed having a length/diameter less than 0.4.

The coils were wound on Distrene rod, diameters ranging from $2\frac{1}{2}$in to $\frac{5}{8}$in. In one case, to attain a sufficiently high length/diameter ratio with a spacing ratio of 0.9, a coil of 20 S.W.G. double-silk-covered wire was wound on a $\frac{1}{4}$-in diameter former. The special virtues of Distrene rod for the present purpose are its low power factor (about 0.0003) and, from the mechanical point of view, the ease with which it can be grooved and the ends of the coil anchored.

The effect of dielectric losses on the total losses may be estimated if we assume that the coil turns are completely embedded in the former. Since in reality, each turn is roughly half surrounded by air and half by former material, we may expect that this assumption will cause us to over-estimate the actual dielectric losses. With this limitation, the percentage increase in the copper-loss series resistance due to dielectric losses is given by

$$\frac{\tau\omega^3 L^2 C_0}{R} \times 100\ \%$$

where τ is the power factor of the former material,
ω is the angular frequency,
L is the coil inductance,
C_o is the coil self-capacitance,
R is the equivalent series resistance due to copper losses.

This may be written as

$$\tau Q(f/f_o)^2 \times 100,$$

where f is the working frequency and f_o the self-resonant frequency,
or as

$$\tau Q(C_o/C) \times 100$$

where C is the tuning capacitance at the working frequency. Q, for the coils measured, was never higher than about 250, and C_o was usually about 3 or 4 pF. Minimum C was about 850 pF. Thus, the maximum value of the percentage dielectric losses that we may expect is

$$\frac{0.0003 \times 250 \times 4 \times 100}{850}$$
$$= 0.035\ \%\ \text{approx.}$$

The ends of the wires (mostly 18 and 20 gauge copper wires) were soldered to leads

of 12 or 14 gauge copper wire, which had been previously tinned and sunk about $\frac{1}{4}$in into the former (using the heat of a soldering iron pressed against the lead just above the former). There is a tendency for the leads to twist in their holes, if they are not bent carefully.

For spacing ratios up to 0.8, the formers were grooved and the coils were wound with bare wire. For a spacing ratio of about 0.9, double-silk-covered wire was wound on ungrooved formers, the turns being as close as possible. This procedure gave spacing ratios ranging from 0.885 to 0.92. One coil (length/diameter = 1.30) was wound with single-silk covered 20 gauge wire (d.s.c. wire, from which the outer layer was stripped) on an ungrooved former, a spacing ratio of about 0.95 being obtained.

There is an appreciable tolerance on wire sold by gauge number, and in any case, the wires are stretched before winding to remove kinks. Consequently, the wire diameter for each coil was taken as the mean of three or four roughly equally spaced measurements, by a centimetre micrometer, along the length of the wire, these measurements being made during the winding.

Each coil was dried for about twelve hours in a desiccator, before measurement.

6. Use of the Twin-T Impedance Measuring Bridge

The twin-T Impedance-Measuring Circuit manufactured by the General Radio Company, Cambridge, Mass., is one of the most recent developments in the technique of measuring high-frequency impedances. Detailed accounts of the theory and its practical application are given in references 10 and 11. We shall very briefly describe its use for the measurement of high-frequency coil impedances.

The twin-T operates over a frequency range from 460 kc/s to 30 Mc/s. It is a null instrument, a balance being obtained by the adjustment of two capacitors. One of these capacitors is calibrated in micro-mhos, and, after multiplying by a factor involving the square of the frequency, gives the effective parallel conductance of the measured impedance. The other, calibrated in picofarads, gives directly the effective parallel capacitance.

The capacitance dial has a range of from 100 to 1,100 pF, and it is calibrated at intervals of 0.2 pF. The scale of the conductance dial is not linear, the calibration intervals ranging from $2\frac{1}{2}$ to 10 per cent of the measured conductance. This dial can usually be read to 1 per cent or better.

In the present series of measurements, the oscillator consisted of a Marconi Signal Generator, covering a frequency range from 85 kc/s to 25 Mc/s. A number of receivers were used from time to time, the necessary qualifications being that the receiver should be well shielded, that it should have a sensitivity of the order of 1 to 10 microvolts, and that it should be provided with a local oscillator to beat with the incoming signal, so as to produce an audible note.

7. Method of Measurement

Each coil was measured over a small band of frequencies at the low-frequency end of the available working range; i.e., at frequencies at which it tuned with capacitances of 800–1,000 pF. There were two reasons for working at the lowest available frequencies: (1) because the conductance-dial reading falls off rapidly as the frequency increases (being inversely proportional to $f^{3.5}$, for the present type of coil) and the error in the reading becomes correspondingly larger, and (2) because the effect of the resistance of the twin-T tuning capacitor is minimum at the lowest frequencies.

Each set of measurements was entered up on a standard sheet. We have reproduced, as a typical example, that relating to coil No. 31. Nine measurements were carried out on each coil, the first at a frequency at which the coil tuned with about 1,000 pF, and the remainder at frequencies increasing progressively by the smallest dial intervals of the signal generator. It was thought preferable to perform each measurement at a different, rather than at the same, frequency to avoid, if possible, systematic errors. The values of $Q/\sqrt{f}$ thus obtained, after various corrections had been made (see over), usually showed a spread of from 3 to 5 per cent.

Various necessary formulae were reproduced, for convenience, on each sheet.

8. Corrections Applied to the Twin-T Measurements

Six corrections had to be applied to the original measurements. Four of them will be described in this section, and the remaining two will be given a section each.

TABLE III

Coil No. 31. 29 . 8 . 45. Mean temperature, 20.5° C.

Freq. Mc/s	C_{p1} (pF)	C_{p2} (pF)	Conductance dial reading	$C_{p2}-C_{p1}$ + 3.4 (pF)	Corrected conductance dial reading	$-\delta G$	True conductance (μmhos)	Q	$\frac{Q}{\sqrt{f}}$	L (μH)
0.78	100	1,080.3	34.9	983.7	21.2	0.1	21.1	228	0.258	42.32
0.79	100	1,056.2	32.9	959.6	20.5	0.1	20.4	233	0.262	42.29
0.80	100	1,031.8	32.0	935.2	20.5	0.1	20.4	230	0.257	42.32
0.81	100	1,007.9	30.8	911.3	20.2	0.1	20.1	231	0.257	42.36
0.82	100	984.8	29.1	888.2	19.6	0.1	19.5	235	0.260	42.41
0.83	100	962.6	28.0	866.0	19.3	0.1	19.2	235	0.258	42.46
0.84	100	943.5	27.0	846.9	19.1	0.1	19.0	235	0.256	42.39
0.85	100	923.4	26.0	826.8	18.8	0.1	18.7	236	0.256	42.40
0.86	100	904.0	25.2	807.4	18.6	0.1	18.5	236	0.255	42.42
								Mean	0.2577	42.37

No. of turns = 40
Wire gauge = 20 s.w.g.
D = 5.19—0.09 cm
= 5.1 cm
R = 2.55 cm
length = 7.01 cm
$\frac{\text{Length}}{\text{diameter}}$ = 1.375
d = 0.0910 cm
$s = \frac{6.92}{39}$ cm

$\frac{d}{s} = \frac{0.0910 \times 39}{6.92}$
$= 0.513$
$Q = \frac{6.283 fC}{G}$
$L = \frac{0.02533}{f^2 C}$
$R_s = \frac{6.283L}{Q/\sqrt{f}}\sqrt{f}$
$\phi = \frac{[(\text{resist})/10^{-6}\ \sqrt{f}] \times d}{0.5218\ Rn}$

$Rexp. = 1{,}033 \times 10^{-6}\sqrt{f}$ ohms
Resistance of leads
$= 7 \times 10^{-6}\sqrt{f}$ ohms
Resistance of coil
$= 1{,}026 \times 10^{-6}\sqrt{f}$ ohms
ϕ = 1.745
= 1.743 at 20° C
= 1.71 at 20° C $f \to \infty$
Resistance of leads
$= 0.1661 \times 10^{-6}\frac{l}{d}\sqrt{f}$
where $l = \frac{1}{2}$ (total length of leads).

8.1. The conductance-dial reading has to be multiplied by a factor of the form $\left(\frac{f}{f_o}\right)^2$, where f is the working frequency and f_o is either 1, 3, 10 or 30 Mc/s according to the frequency range which is used. The results of this correction are in column 6 of the measurements sheet.

8.2 The corrected conductance value thus obtained has to be further corrected on account of the resistance, R_c, of the metal structure of the main capacitor. According to Sinclair's paper,[11] R_c, in a twin-T whose residual parameters were measured by him, had the value 0.025 ohm at 30 Mc/s. As will be shown later, even a large departure from this value in the machine actually used, will not seriously affect the present measurements. Assuming this resistance to be proportional to the square root of the frequency, the error it introduces into the conductance reading can be corrected by adding algebraically a factor δG, which has the form

$$\delta G = -\{0.184(f)^{2.5}\}(C_{p2}^2 - C_{p1}^2) \times 10^{-6}\ \mu\text{mhos}.$$

f represents the frequency (Mc/s), and C_{p1} and C_{p2} are respectively the initial and final settings of the tuning capacitor (pF).

This is a very cumbersome expression to use, if one has to work out a large number of values of δG. The labour of evaluation can be considerably decreased by using a graphical procedure. The first part of the expression, $0.184(f)^{2.5}$, is plotted on double-logarithmic graph paper (Fig. 2), for a range of f from 0.1 to 10. The second part, $(C_{p2}^2 - C_{p1}^2) \times 10^{-6}$, is plotted as the third line of a nomograph (Fig. 3) the two base lines being C_{p1} and C_{p2}, each ranging from 100 to 1,150 pF. δG is now obtained as the product of the two quantities read off from Figs. 2 and 3.

As an example: for coil No. 31, at a frequency of 0.78 Mc/s C_{p1} was 100 pF, and C_{p2} 1,080.3 pF.

Now, $0.184(f)^{2.5} = 0.184(0.78)^{2.5}$
$= 0.1$ from Fig. 2

and $(C_{p2}^2 - C_{p1}^2) \times 10^{-6} = 1.16$ from Fig. 3
so $\delta G = -0.1 \times 1.16$
$= -0.1\ \mu$mho approx.

While the value of R_c, for the particular twin-T used, was probably not identical with that of the twin-T measured by Sinclair, it was not thought necessary to repeat Sinclair's measurements. There were two reasons for this: (1) the correction for R_c, at the frequencies used, is a small fraction of the

measured conductance (usually of the order of 1 or 2 per cent), and the correction would not be appreciably affected by any likely deviation of R_c from Sinclair's value, and (2) the value assumed for R_c, at frequencies of the order of 1 Mc/s is, in any case, an approximation, since R_c has to be measured at a frequency round about 30 Mc/s and the doubtful assumption is made that R_c will vary precisely as the square root of the frequency.

8.3 The correction for losses in the leads is most conveniently applied by subtracting it from the equivalent series resistance. The expression for the h.f. resistance of a straight




Fig. 2. *Correction for R_c (1).*

isolated copper wire was considered a good enough approximation to this loss. The correction was usually less than 1 per cent of the total series losses.

8.4 Temperature variation of the dimensions of the coils will not produce an appreciable effect on the series resistance over the temperature range (from about 16° to 26° C) encountered. However, temperature variation of resistivity has to be taken into account. Taking the temperature coefficient of resistivity of copper as 0.0039 at 20° C, we have to multiply the apparent value of ϕ (the ratio of the coil resistance to the resistance of the same length of straight wire at




Fig. 3. *Correction for R_c (2).*

the same frequency) by one of the following factors.

$$\frac{1}{\sqrt{1 + 0.0039(t - 20)}} \quad \text{if } t > 20^\circ \text{ C}$$

or $\sqrt{1 + 0.0039(20 - t)}$ if $t < 20^\circ$ C

where t°C is the temperature of measurement.

8.5 The remaining two corrections are (5), for coil self-capacitance and (6), a frequency correction to the final value of ϕ. We shall consider each of these in a separate section.

(To be concluded)

For references see end of article in March issue.

H.F. RESISTANCE AND SELF-CAPACITANCE OF SINGLE-LAYER SOLENOIDS

By R. G. Medhurst, B.Sc.

(Communication from the Staff of the Research Laboratories of The General Electric Company, Limited, Wembley, England.)

(Concluded from page 43 of the February issue.)

9. Self-capacitance of Single-layer Coils.

9.1. The self-capacitance of each coil, including capacitance due to leads, has to be added to the parallel capacitance reading of the twin-T. It is a small correction, usually less than 1 per cent. The original intention was to use Palermo's formula for self-capacitance[14], this being available in abac form[18] and hence readily made use of. However, for the closely-spaced coils, a noticeable variation with frequency started to appear in the calculated values of inductance (which should be consistent to better than $\frac{1}{2}$ per cent), so it was decided that an attempt should be made to find out whether Palermo's formula did in fact agree with experiment, and, if there was a substantial disagreement, whether an empirical formula could be substituted.

What was required was a set of formulae, or, preferably, a set of curves from which the self-capacitance of a particular coil could be quickly and easily read off, say to 20 per cent or better. Since the capacitance of the leads is of the same order of magnitude as that of the coil, it was first necessary to find out whether the lead capacitance could be specified by some quantity which would be additive algebraically to the self-capacitance of the coil.

The simplest hypothesis is that the " live " lead can be treated as an isolated straight vertical wire ; that is to say, that (1) the fact of its being bent, and (2) the proximity of the coil to the upper end have a negligible effect on its capacitance. This we shall show to be correct, to the degree of approximation we require.




Fig. 4. *Variation with length of capacitance of vertical 12 gauge copper wire.*

9.2. The capacitances of a number of copper wires of various lengths and diameters, from 10 to 40 cm in length and from 12 S.W.G. to 44 S.W.G., were measured at 200 kc/s, the wires standing vertically upright with their lower ends in the live terminal of a Cambridge Capacity Meter. Over this range of length, the capacitances of each wire gauge were quite closely proportional to their lengths (see, for example, Fig. 4).

The capacitances, measured in this way, of 25-cm lengths of wire of various gauges are plotted against the wire diameter in Fig. 5. In Fig. 6 capacitance is plotted against length for a number of wire gauges.*

We may readily show that bending of the wire and alteration of its position relative to earth make no large difference to the measured capacitance. A 25-cm length of No. 12 S.W.G. copper wire was measured in a vertical position, as before. Its capacitance was 2.9 pF. Now, a piece of brass sheet, 35 cm × 15 cm, was attached to the earth terminal of the capacitance meter, so that it formed a horizontal earth




Fig. 5. *Capacitance of 25-cm lengths of vertical copper wire of various diameters.*




Fig. 6. *Variation of capacitance with wire length for vertical copper wires of various gauges.*

adjacent to the wire in the live terminal. The wire was bent over so that about 2/3 of its length was horizontal and about 6 cm above the brass sheet. The capacitance was now 3.0 pF. Even when the wire was brought to within about 2 cm of the earth plate, the capacitance reading only rose to 3.6 pF. Finally, the wire was screwed into the meter terminal at its centre, the two ends being bent up to about 45° to the horizontal. The capacitance reading was now 3.1 pF.

Some of these measurements were repeated on the twin-T, at frequencies up to 20 Mc/s, and close agreement was obtained. In addition, some observations were made on the effect of the proximity of an adjacent vertical earth lead, screwed into the earth terminal of the twin-T. It was found that there was no measurable increase in capacitance until the earth lead was brought to within one or two centimetres of the live lead.

9.3. Before we discuss the effect of the proximity of the coil on the capacitance of the "live" lead, we have to describe the method used for measuring the capacitance of the whole coil-lead assembly.

The standard technique for making self-capacitance measurements on coils was originally suggested by G. W. O. Howe[17]. The square of the wavelength is plotted against the added parallel capacitance necessary to resonate the coil. The points so obtained should lie on a straight line, which is produced to meet the capacitance axis, making a negative intercept which is numerically equal to the self-capacitance. The present method is a modification of this, making use of the large range (1,000 pF) of the main tuning capacitor of the twin-T and its fine graduation (0.2 pF per division). A measurement is carried out at the frequency at which the coil resonates with about 1,000 pF. About half a dozen additional measurements are now required, the first at about four times this frequency and the remainder at frequencies increasing in steps of 2 or 3 Mc/s.

Now, if we know the self-capacitance (including lead capacitance), we can calculate the inductance from any one of these measurements, since the coil is resonating with its self-capacitance plus the added capacitance. To obtain a given accuracy of inductance

* It is interesting to note that, over these ranges of length and diameter, the theoretical expression, given originally by G. W. O. Howe (see ref. 19: also ref. 12 p. 116), for capacitance of a straight vertical wire above a plane earth is very roughly linear with respect to the length of wire. Our experimental points, however, fit more closely to a straight line than to this theoretical curve. The theoretical curve for 12-gauge wire intersects the experimental straight line at the 45-cm length point and is about 0.4 pF above at a length of 10-cm. In the 20-gauge case, the theoretical curve falls above the experimental line throughout the range, the maximum deviation being about 0.3 pF.

we need to know the self-capacitance less accurately as the added capacitance becomes higher. In particular, if we make use of the measurement involving an added capacitance of about 1,000 pF, quite a rough value of the




Fig. 7. *Apparent self-capacitance of a coil with various lengths of leads.*

self-capacitance (which is not usually greater than 5 pF) will yield an inductance value of very high accuracy. The rough value is derived from the 1,000-pF measurement and the measurement involving the lowest added capacitance. In practice, we do not actually work out this self-capacitance correction, the inductance being obtained directly from the formula

$$L = \frac{0.02533}{C_2 - C_1}\left[\frac{1}{f_2^2} - \frac{1}{f_1^2}\right]$$

C_1 and C_2 (pF) being the added capacitances at frequencies f_1 and f_2 Mc/s) respectively.

Finally, using this value of inductance we can calculate the self-capacitance, at each of the frequencies of measurement after the first, from the formula

$$C_0 = \frac{0.02533}{Lf^2} - C$$

where C is the added capacitance at frequency f.

As an example of this method, coil No. 32 had 38 turns of 20 S.W.G. copper wire, mean diameter being 5.10 cm, overall length 4.79 cm, spacing ratio 0.720. Self-capacitance measurements took the form shown in Table IV.

The live lead consisted of 10 cm of 14 S.W.G. copper wire. Thus, a lead capacitance of 1.03 pF (independent of frequency) has to be subtracted from each of the readings in Table IV, to give the actual self-capacitance of the coil (see below, Sections 9.4 and 9.6). The mean self-capacitance now becomes 2.30 pF.

It appears, from these results, that the reactance of this coil can be represented closely, over quite a wide frequency range up to and beyond the self-resonant frequency, by a fixed inductance in parallel with a fixed capacitance. This is true for all the coils measured, no evidence being found for the suggestion sometimes made (e.g., ref. 12, p. 84, footnote) that self-capacitance is lower at the self-resonant frequency of the coil than at frequencies much less than this.

9.4 Now we can return to the question of the effect of the lead capacitance on the total measured capacitance.

TABLE IV.

Frequency Mc/s	C_1 (pF)	C_2 (pF)	C	L		C_0
			$C_2 - C_1$ (pF)	Inductance (μH)	$\frac{0.02533}{Lf^2}$ (pF)	$\frac{0.02533}{Lf^2} - C$ (pF)
0.72	100	1076.0	976.0	49.89		
3.0	100	153.2	53.2		56.4	3.2
6.0	200	210.7	10.7		14.1	3.4
8.0	150	154.6	4.6		7.9	3.3
12.0	200	200.15	0.15		3.52	3.4
15.0	300	298.95	−1.05		2.25	3.3
18.0	200	198.2	−1.8		1.57	3.4
					Mean.	3.33

A coil was constructed (39 turns of 20 gauge wire, mean diameter 5.08 cm, overall length 4.70 cm) having 14 gauge leads each 35 cm in length, inclusive of the portion bent over near the twin-T terminals. The parallel capacitance of coil plus leads was measured as just described, and the measurements repeated when the leads were shortened to 23.5, 11.5 and 7.5 cm.

The results are plotted, in Fig. 7, against the length of the live lead. If the lead capacitance adds algebraically, without modification, on to the coil self-capacitance, these points should lie on a straight line




Fig. 8. *Comparison between Palermo's formula and measured self-capacitances of coils having length/diameter = 1 approximately.*

parallel to the 14 S.W.G. line of Fig. 6. By the method of least squares, the best fitting straight line has been drawn among these points, which deviate from it by not more than 5%. This line, it will be seen, is very closely parallel to the 14 S.W.G. line.

9.5. We are now in a position to deal with Palermo's self-capacitance formula. Previous work [14–17,20] has established that the self-capacitance of a single-layer coil (C_0) is directly proportional to the coil diameter. It is also independent of the number of turns, provided this number is not too small. The remaining quantities upon which C_0 might depend are the ratio of coil length to diameter, the wire diameter (d) and the spacing of the turns (s). Investigators before Palermo had assumed that C_0 was independent of d and s. Palermo asserted that C_0 varied with d and s according to the following relation:

$$C_0 = \frac{\pi D}{3.6 \cosh^{-1} s/d}$$

where D is the coil diameter (cm).

This result, independent of the length of the coil, was supposed to hold for coils whose length/diameter ratio was equal to or less than 1.

Fig. 8 shows measured values of the ratio C_0/D for nine coils having diameters ranging from 2.6 to 6.4 cm and spacing ratios (d/s) from 0.15 to 0.95. Wire gauges used range from 18 to 30 S.W.G. All the coils were wound with bare wire on grooved Distrene formers except two, with values of d/s equal to 0.947 and 0.919, which were wound respectively with single-silk-covered and double-silk-covered wire on ungrooved Distrene rod, the turns being as close together as possible. Values of length/diameter were all about 1, ranging from 0.94 to 1.49. Each coil was measured as described above (see Table IV), lead capacitances being subtracted. In Fig. 8, Palermo's theoretical expression for C_0/D is plotted against d/s, and the experimental values are plotted on the same scale. To better than 5%, the measured values fit the expression

$$C_0 = 0.46\ D,$$

being independent of the spacing ratio. These observed values show a tendency to increase slightly with increasing proximity of turns, but this increase was of the order of magnitude of the experimental error anticipated, and it was not thought than any useful conclusions could be drawn.

It has to be pointed out that this experimental demonstration of the lack of dependence of self-capacitance on the spacing of turns contradicts not only Palermo's theory but also some experimental confirmation which he brought forward (see Section 9.7 below.) Consequently, it seems advisable to remark that no investigators other than Palermo have found a measurable variation with turn spacing. J. C. Hubbard [16], for example, says:




Fig. 9. *Variation of self-capacitance with coil length (one end of coil earthed).*

"There is no evidence that the variation of ratio of pitch to diameter of wire has a measurable effect on the distributed capacity in the region studied, though some effect is to be expected for coils of a smaller number of turns than those studied here." Hubbard's minimum number of turns was 35, and he worked down to a length/diameter of about 0.2; i.e., his coils are "short" enough for Palermo's formula to be applicable.

9.6. C_0 having been shown to be substantially independent of d/s, the final step is to find the variation of C_0 with the length/diameter ratio. Fig. 9 shows the results of a series of measurements on coils whose length/diameter ranged from 29.2 to 0.163. Diameters ranged from 0.675 to 6.36 cm, and numbers of turns from 10 to about 636. All the coils were those which had been used for h.f. resistance measurements, except the two with the greatest and smallest ratios of length/diameter. The former was wound with about 636 turns of 34 gauge wire, double-silk-covered, on a $\frac{1}{4}$-in Distrene former, and the latter with 10 turns of 20 gauge wire, double-silk-covered, on a $2\frac{1}{2}$-in Distrene former.

It appears that, in the commonly occurring case when one end of the coil is at earth potential, we can write down the self-capacitance in the form

$C_0 = HD$ picofarads, where D is in centimetres.

H depends on the length/diameter ratio only. The table of values of H which follows is based on the curve of Fig. 9. The use of these values, with the appropriate lead correction, should give results accurate to 5% or better.

TABLE V.

Length / Diameter	H	Length / Diameter	H	Length / Diameter	H
50	5.8	5.0	0.81	0.70	0.47
40	4.6	4.5	0.77	0.60	0.48
30	3.4	4.0	0.72	0.50	0.50
25	2.9	3.5	0.67	0.45	0.52
20	2.36	3.0	0.61	0.40	0.54
15	1.86	2.5	0.56	0.35	0.57
10	1.32	2.0	0.50	0.30	0.60
9.0	1.22	1.5	0.47	0.25	0.64
8.0	1.12	1.0	0.46	0.20	0.70
7.0	1.01	0.90	0.46	0.15	0.79
6.0	0.92	0.80	0.46	0.10	0.96

J. C. Hubbard[16] remarked: "... we apparently have two quite independent factors" (determining the self-capacitance of coils), "one predominating greatly in very short coils, the other, in very long coils." It is an interesting confirmation of this suggestion that the experimental results of Fig. 9 and Table V can be fitted quite closely (to 2 or 3%) by an expression of the form

$$H = 0.1126\,\frac{l}{D} + 0.08 + \frac{0.27}{\sqrt{l/D}}$$

The first numerical factor follows from Nagaoka's inductance formula for long coils and the experimental fact that the self-resonant wavelength for long coils equals twice the length of winding (see below). The other two factors are empirical.

A few additional measurements were made on some two-turn and single-turn coils. A coil of two turns of closely-spaced 18 S.W.G. double-silk-covered wire, diameter 6.47 cm, length/diameter 0.042 gave an H value of 1.53, which is quite close to the value, 1.40, calculated from the expression above. Another two-turn coil, of closely-spaced double-silk-covered 40 gauge wire, diameter 4.46 cm, length/diameter 0.0067, gave the low H value of 0.96. The lead correction is uncertain in both these cases, the assumptions about the live and the earth leads needing modification when the length of the lead becomes comparable with the winding length. It seems from these results that the curve of Fig. 9 can be extrapolated to a length/diameter of about 0.05, even when the number of turns is only two, but that there is a considerable falling off thereafter. A one-turn coil (14 S.W.G., mean diameter 23.9 cm, length/diameter 0.0084) departed even more from the trend of the curve in Fig. 9, the H value being only 0.23.

As an example of the use of Fig. 6 and 9, we may take the coil dealt with in Table III. Ratio of length to diameter was 1.375, and mean diameter was 5.10 cm. Hence, from Fig. 9,

self-capacitance of coil $= 5.10 \times 0.47$
$= 2.4$ pF.

The leads were of 14 S.W.G., the length of each was 9.5 cm. Hence, from Fig. 6,

capacitance of live lead $= 1.0$ pF

Thus, total capacitance $= 2.4 + 1.0$ pF
$= 3.4$ pF.

9.7 The wide discrepancy between

Palermo's results and the present work make it desirable to say something about the theoretical basis of the expression put forward by Palermo.

What is called the "self-capacitance" of a coil will actually be a composite quantity, and the components will not necessarily be mutually dependent. It is convenient, to begin with, to divide coil self-capacitance into two parts, the "internal" and the "external" capacitances. When a current flows through the coil, each turn is at a different mean potential from every other turn. Consequently, there will be capacitances between each pair of turns (modified by the presence of the other turns between or on either side of the particular pair.). We shall call the effective parallel capacitance, across the whole coil inductance, the "internal" capacitance; it is formed by summing all these capacitances between turns, each taken across the appropriate part of the inductance.

Furthermore, each turn will be at a mean potential different from that of the earth, so that each turn will show a capacitance to earth. The effective parallel capacitance formed by summing these capacitances to earth we shall call the "external" capacitance.

It will be apparent that if the external and internal capacitances are comparable in magnitude, the apparent self-capacitance will be different when neither end of the coil is earthed, since the external capacitance will then not appear directly across the terminals of the coil. Hence, the present results, which are all for coils earthed at one end, may not be applicable to coils both ends of which are above earth potential.

Palermo further divides the internal capacitance into two portions, the capacitance between adjacent turns and the capacitance between turns which are not adjacent. He assumes that almost the whole of the self-capacitance is made up of the portion of the internal capacitance between adjacent turns: that is to say, he asserts that the capacitance between non-adjacent turns will be negligible, and he fails to mention the external capacitance.

Now, in spite of having neglected what may be a large part of the total self-capacitance, he predicts values which, for closely spaced coils, are very much larger than the values we have measured. The reason for this over-estimate is not too difficult to see.

Palermo derives his capacitance between adjacent turns from the formula for the capacitance between long parallel cylinders, diameter d and separation of centres s, which he quotes in the form

$$C = \frac{1}{3.6 \cosh^{-1} s/d} \text{ picofarads/cm.}$$

When s/d approaches 1, that is to say, when the cylinders are very close, this expression approaches infinity. However, when the turns of a coil are very close the self-capacitance does not approach infinity, and the reason for the discrepancy appears to be that what we have to concern ourselves with is the effective current-carrying path and not the whole of the cross section of each turn.

When high-frequency current flows through an isolated wire, the current tends to be concentrated near the surface. When the wire is bent into the form of a coil, the current tends, further, to flow round the inner surface of the coil. Finally, the effect of the adjacent turns is to cause the current to withdraw from the portions of the wire nearest to these turns. Thus, even when the turns are very close the effective current-carrying paths are still comparatively remote from each other.

Thus, the capacitance between adjacent turns will be less than that predicted by Palermo. The fact that self-capacitance is substantially independent of spacing of turns suggests that the part of the self-capacitance considered by Palermo is actually negligible.

The question of the validity, or otherwise, of Palermo's formula is complicated by the existence of some measurements (on coils earthed at one end) which he brings forward in support of his theory. It is difficult to say much about these measurements, except that they are closely in agreement with Palermo's formula, and consequently, when the turns are closely spaced, they are very different from other published results on similar coils. The discrepancy is drastically illustrated by Palermo's coil No. 9, which had a diameter of 10.40 cm and a length of 9.65. The number of turns was 28, the wire diameter 0.326 cm and the spacing ratio 0.94. The coil was measured at a "high frequency"; i.e., at something below, but of the order of magnitude of the self-resonant frequency. From the curve of Fig. 9 we would predict a self-capacitance of

4.8 pF. Palermo's formula gives 20.5 pF. The measured value he gives as 20.0 pF.

Palermo's measured coils fall into two groups. Seven of them, with spacing ratios between 0.3 and 0.8 were measured by the Bureau of Standards. Over this region of spacing ratio, Palermo's " proximity effect " is not too pronounced. The measured values were all between 1 and 3 picofarads larger than the values that would be predicted from our present work. Palermo makes no mention of a correction for leads and terminals, and possibly this accounts for the discrepancy. The remaining twelve coils were measured by Palermo himself, and it is among these that we find the capacitances (such as the one already quoted) which are so greatly different in magnitude from our results.

9.8. We have seen that, so far as self-capacitance is concerned, a single-layer coil behaves very closely like a cylindrical current sheet. It is well known that this is also true of the inductive part of its reactance. If we combine these two current-sheet formulae we might expect to deduce some simple expression, depending on the coil geometry, for the self-resonant frequency.

Our measurements have given a self-capacitance expression in the form

$C_0 = HD$, where H is a quantity dependent on the length/diameter only.

The Nagaoka expression for the inductance, L_0, may be written in the form

$L_0 = Kn^2D$, where K is dependent on the length/diameter only.

Now, if we call λ (cm) the self-resonant wavelength, we have

$\lambda = 2\pi c \sqrt{L_0C_0}$ where c (cm/sec) is the velocity of electro-magnetic radiation,

$= 2\pi c \sqrt{HKn^2D^2}$

$= 2\pi c\, nD \sqrt{HK}$

$= Nl$ where N is dependent on the length/diameter only and l is the total length of wire.

Values of N, worked out from the inductances and self-capacitances of the coils previously measured, are plotted against length/diameter in Fig. 10. Table VI gives values of N and has been worked out from Table V and Nagaoka's values of K.




Fig. 10. *Wavelength at self-resonant frequency equals $N \times$ total length of wire.*

TABLE VI.

Length / Diameter	N	Length / Diameter	N	Length / Diameter	N
50	2.0	5.0	2.3	0.70	3.8
40	2.0	4.5	2.4	0.60	4.0
30	2.0	4.0	2.4	0.50	4.3
25	2.0	3.5	2.5	0.45	4.5
20	2.0	3.0	2.5	0.40	4.8
15	2.1	2.5	2.6	0.35	5.0
10	2.1	2.0	2.7	0.30	5.4
9.0	2.1	1.5	2.9	0.25	5.8
8.0	2.2	1.0	3.4	0.20	6.3
7.0	2.2	0.90	3.5	0.15	7.1
6.0	2.3	0.80	3.6	0.10	8.3

10. Frequency Correction.

The measured values of ϕ (ratio of the h.f. resistance of the coil to the resistance of the straightened wire at the same frequency) are mostly for frequencies such that z (see list of symbols) has values between 8 and 20. Though these frequencies are to be regarded as " high " according to our previous definition of " high frequency," (i.e., frequency for which $z>7$), ϕ will still, to some small extent, be frequency dependent. So that the measured values shall be comparable among themselves, it will be advantageous to apply a frequency correction such that the corrected ϕs correspond to the same value of z. If we choose infinity as this standard z value the corrected ϕs can be compared directly with Butterworth's "high-frequency" table, which is supposed to apply at infinitely large z. Since, as we shall see, the frequency correction is small, we may still use the corrected ϕ values at the orders of frequency commonly encountered.

It is unfortunate that exact measurements on coil resistance are almost as scarce at

low as at high frequencies. Consequently, it has not been found possible to deduce from previous work an experimental frequency correction to convert the present measurements from "high" to "infinite" frequency. Tentatively, a correction formula was used based on Butterworth's theoretical considerations, modified in the light of the present results. The formula in question is

$$\Delta\phi = \frac{1}{8G}(\phi_{exp} - 2\alpha)$$

ϕ_{exp} being the measured value of ϕ, and G and α being quantities due to Butterworth (see, e.g., ref. 12, pp. 78 and 79).

The correction did not usually exceed 2%. It may be either positive or negative. In deriving $\Delta\phi$, the general form of Butterworth's resistance formula is assumed; i.e.,

$$\frac{\text{a.c. resistance}}{\text{d.c. resistance}} = \alpha H + kG$$

where the first term represents the losses due to the currents in the wires, and the second the losses due to the field of the whole coil. H and G are functions of z only, being given for large z by $\frac{\sqrt{2}z + 1}{4}$ and $\frac{\sqrt{2}z - 1}{8}$ respectively (the value of z chosen for each coil being that corresponding to the mean working frequency). α depends on the spacing ratio of the turns, and k on the spacing ratio and the dimensions of the coil.

Now, we have seen previously (Section 3.2) that the Butterworth theory is most open to suspicion in that part of it which deals with losses due to the "mean transverse field." The effect of these losses, in the theory, is to cause k, at infinitely high frequency, to have very high values, especially for close spacing. This is the effect that is not confirmed by the present measurements. So, to derive a frequency-correction formula, we shall assume that k has some value which does not vary with frequency (z being sufficiently high) and, eliminate k between the expressions for ϕ at the frequency of measurement and at infinite frequency. α we may take, according to the theory, as being also very nearly invariable with frequency.

When z approaches infinity, we have

$$\phi = \alpha + \frac{k}{2}$$

$$\text{Also, } \phi_{exp} = \frac{\text{a.c. resistance}}{\text{d.c. resistance}} \cdot \frac{1}{\sqrt{2}z/4}$$

$$= 4\,\frac{\alpha H + kG}{(8G + 1)}$$

and hence, eliminating k from the expressions for ϕ and ϕ_{exp} and using the relation $2H = 1 + 4G$, we obtain the required expression for ϕ; i.e.,

$$\phi = \phi_{exp} + \frac{1}{8G}(\phi_{exp} - 2\alpha)$$

We shall see later that the argument for assuming k to be substantially independent of frequency, when z is high enough, is not complete, because we have only given reasons for rejecting that part of Butterworth's theory which applies to *high*-frequency coil resistance. We shall consider the low-frequency case in Section 14.

11. Effect of the Proximity of the Twin-T Top.

It was thought that an additional correction might be necessary for losses due to the proximity of the metal top of the twin-T. To ascertain the order of magnitude of this effect, a coil (48 turns of 20 gauge d.s.c. wire, mean diameter 2.70 cm, length/diameter 1.82, d/s 0.89) was measured a number of times, the leads being progressively shortened until the distance of the coil from the twin-T terminals was about its own diameter. The coil was then about 2 diameters above the twin-T top.

There was no significant variation in the

TABLE VII.

Length of each lead cm	Total Resistance ohms	Temperature °C	Total Resistance at 20° C ohms	Resistance of leads (20° C) ohms	Resistance of coil (20° C) ohms
40	$1219 \times 10^{-6}\sqrt{f}$	24	$1210 \times 10^{-6}\sqrt{f}$	$25 \times 10^{-6}\sqrt{f}$	$1185 \times 10^{-6}\sqrt{f}$
15.5	1204 ,,	24	1195 ,,	10 ,,	1185 ,,
8	1212 ,,	25	1200 ,,	5 ,,	1195 ,,
8	1218 ,,	26.5	1203 ,,	5 ,,	1198 ,,
4.5	1211 ,,	27	1195 ,,	3 ,,	1192 ,,

measured resistances, their spread being about 1 per cent. The results are given in Table VII.

The two 8-cm measurements were carried out on successive days. The length of each lead includes the right-angle bend at the twin-T terminal, so that in the case of the last measurement the coil was about 2.5 to 3 cm above the terminal.

12. Results of Measurements.

After all these corrections have been applied, we are left with a set of experimental values of ϕ for various non-integral values of coil length/diameter and d/s. These have to be reduced to a table with the same intervals as those of Table I.

We are assisted in this process by remembering that the error in Butterworth's values has been assumed to be due to excessive weight being given to the transverse field losses. If we work out Butterworth's formula again neglecting the transverse field we obtain another table whose entries are all less than those in the Butterworth table, except for the column corresponding to infinite length/diameter. In this case, the transverse field has disappeared.

Our experimental values all lie between these two sets of values. Consequently, we shall take the case where these two sets of values are equal, i.e. the extreme right-hand column, as the limiting case of our empirical table. This is convenient, because it is not possible to measure coils whose length/diameter is infinite.

Further, measurements on a few coils whose length/diameter ratio was about 8, showed that the experimental values of ϕ were within 1 or 2 per cent. of the Butterworth values when the transverse field is neglected. Since transverse-field effects are less appreciable as the length/diameter ratio increases, we may use this result to fill in the 8 and 10 length/diameter columns.

Measurements on several coils having values of $d/s = 0.2$ and 0.3, with length/diameter ranging from 0.5 to 4, showed that Butterworth's values for these two rows are confirmed by the experimental results. This was used to fill in the three lowest rows, it being assumed that the bottom row, the values in which are close to those for a straight wire, could safely be taken as following Butterworth.

It may be pointed out that this agreement with Butterworth's figures, over the region in which Butterworth's theory might be expected to hold, constitutes indirect evidence of the reliability of the measurements.

There remains the most important portion of the table, that is, the top left-hand quadrant. In general, due to difficulties in accurate grooving, the spacing ratios were not exact multiples of 0.1. However, the spacing ratios of the coils which had been constructed to have $d/s = 0.6$, turned out to be very close to the value aimed at. A smooth curve could thus be drawn through their ϕ values, giving the sixth row from the bottom. By extrapolating the values of coils having d/s about 0.5 and 0.7, using this $d/s = 0.6$ row and then drawing smooth curves, the adjacent rows were obtained, and similarly for the rest of the table.

The final result is Table VIII. The values for $d/s = 1$ are obtained by extrapolation. So are the values for the two left-hand columns.

In general, the experimental points deviate

TABLE VIII.

d/s	Coil Length/Coil Diameter											
	0	0.2	0.4	0.6	0.8	1.0	2	4	6	8	10	∞
1.0	5.31	5.45	5.65	5.80	5.80	5.55	4.10	3.54	3.31	3.20	3.23	3.41
0.9	3.73	3.84	3.99	4.11	4.17	4.10	3.36	3.05	2.92	2.90	2.93	3.11
0.8	2.74	2.83	2.97	3.10	3.20	3.17	2.74	2.60	2.60	2.62	2.65	2.81
0.7	2.12	2.20	2.28	2.38	2.44	2.47	2.32	2.27	2.29	2.34	2.37	2.51
0.6	1.74	1.77	1.83	1.89	1.92	1.94	1.98	2.01	2.03	2.08	2.10	2.22
0.5	1.44	1.48	1.54	1.60	1.64	1.67	1.74	1.78	1.80	1.81	1.83	1.93
0.4	1.26	1.29	1.33	1.38	1.42	1.45	1.50	1.54	1.56	1.57	1.58	1.65
0.3	1.16	1.19	1.21	1.22	1.23	1.24	1.28	1.32	1.34	1.34	1.35	1.40
0.2	1.07	1.08	1.08	1.10	1.10	1.10	1.13	1.15	1.16	1.16	1.17	1.19
0.1	1.02	1.02	1.03	1.03	1.03	1.03	1.04	1.04	1.04	1.04	1.04	1.05

Experimental values of the ratio of the high-frequency coil resistance to the resistance at the same frequency of the same length of straight wire.

from the smoothed curves by 1 or 2 per cent. In three cases the deviation is as high as 3 per cent.

It has already been pointed out (Section 5) that, from physical considerations, it becomes increasingly difficult to construct coils fulfilling the various criteria of Butterworth's h.f. resistance table as one approaches the extreme left-hand side of the table. The difficulty becomes acute in the bottom left-hand quadrant. To cover this region, it was necessary to sacrifice the condition that z should be high. Thus, coil No. 41, which had a mean diameter of 6.24 cm, length/diameter of 0.542, and d/s of 0.266, had to be wound with 30 gauge wire, and z was only 2.79. The correction for frequency was now about 17 per cent. This, however, is not too alarming because in this region Butterworth's formulae predict values of α and k (in the Butterworth expression for ϕ, given above) which are almost independent of frequency for large z.

The entries of Table VIII are shown graphically in Fig. 11. For closely spaced wires, there is a critical value when the length/diameter ratio is about 1. This may have some connection with the parallel phenomenon observable in the case of the self-capacitance (see Fig. 9).




Fig. 11. *Variation of θ with spacing ratio and length/diameter ratio.*

$$\theta = \frac{\textit{h.f. resistance of coil}}{\textit{h.f. resistance of same length of straight wire at same frequency}}$$

13. Variation of Q with Coil Shape.

It is not very easy to judge coil performance from figures connected with the h.f. resistance. Normally, we are concerned with coil efficiency, which may best be defined by its Q value at a particular frequency.

It is well-known that Nagaoka's inductance formula may be used, with an error of not more than 5%, up to quite high frequencies. In fact, in the case of the coils used in the present series of measurements, if we assume a constant self-capacitance the inductive part of the reactance agrees closely with Nagaoka's value up to the self-resonant frequency. It breaks down most seriously when the wire diameter becomes comparable (of the order of 1/10th or more) with the coil diameter.

Nagaoka's inductance formula is usually written in the form

$$L_x = \frac{4\pi^2 R^2 n^2 K \, 10^{-9}}{l} \text{ henrys}$$

where R, l and n have the meanings previously defined, and K is a factor involving the ratio of length/diameter only.

Also, R_x = (d.c. resist.). H . ϕ ohms.

where H has its high-frequency value (see Section 10) and ϕ is defined by Table VIII.

Hence,

$$R_x = \frac{2\pi Rn}{\pi(d/2)^2}\,\rho \cdot \frac{1}{2\sqrt{2}}\,\pi d\sqrt{\frac{2f}{10^9\rho}} \cdot \phi \text{ ohms.}$$

$$= \frac{\sqrt{2}\,Rn\,\rho}{\beta d}\,\phi \text{ ohms,}$$

where

$$\beta = \frac{1}{2\sqrt{2\pi}}\sqrt{\frac{10^9\rho}{f}}$$

Now,

$$Q = \frac{2\pi f\,L_x}{R_x}$$

$$= 2\pi f \cdot \frac{4\pi^2 R^2 n^2}{l} K10^{-9} \cdot \frac{\beta d}{Rn\rho\,\phi\,\sqrt{2}}$$

$$= \frac{\pi R}{\sqrt{2}\beta} \cdot \frac{nd}{l} \cdot \frac{K}{\phi}$$

$$= \frac{R}{\sqrt{2}\,\beta}\,\frac{\pi d}{s} \cdot \frac{K}{\phi}$$

$$= \frac{R}{\sqrt{2}\beta}\,\psi \text{ where } \psi \text{ is a function of } d/s \text{ and } l/D.$$

For copper, taking $\rho = 1.7 \times 10^{-6}$ ohm-cm we find that

$$Q = 0.15R\,\psi\,\sqrt{f}$$

Table IX, which gives values of ψ for various values of coil length/diameter and spacing ratio, is derived from Table VIII and Nagaoka's table of K. The measured values of Q (uncorrected for leads) were checked against those predicted from this table. For coils falling within the body of the table, that is to say, to the left of the column length/diameter = 4, the difference was 5 per cent. or less, the values based on Table IX being usually higher than the experimental values. For coils with length/diameter = 5 or more, and d/s greater than 0.5, the measured values tended to be 10 per cent or more lower than the predicted values.

The discrepancy in the case of the long coils is due not to divergence of the measured resistances from the values corresponding to Table VIII but to inductance values different from those predicted by Nagaoka's formula. These coils all had small diameters, in order that a sufficiently large length/diameter ratio could be attained without excessive bulk of coil, and the wire diameter could no longer be regarded as small compared with the coil diameter. Now, Nagaoka's formula is a current-sheet formula and assumes that the thickness of this sheet is negligible compared with the diameter. In using Nagaoka's formula, we have taken the mean diameter of our coil as the diameter of his equivalent current-sheet. However, the current in a coil, at high frequencies, tends to flow round the inner surface, so that the equivalent current-sheet should




Fig. 12. *Variation of optimum spacing ratio with length/diameter.*

TABLE IX.

d/s	Coil Length/Coil Diameter											
	0	0.2	0.4	0.6	0.8	1.0	2	4	6	8	10	∞
1.0	0.00	0.18	0.26	0.31	0.35	0.38	0.63	0.80	0.89	0.93	0.93	0.92
0.9	0.00	0.24	0.33	0.39	0.43	0.47	0.69	0.84	0.90	0.93	0.93	0.91
0.8	0.00	0.28	0.40	0.46	0.50	0.55	0.75	0.87	0.90	0.91	0.91	0.89
0.7	0.00	0.32	0.46	0.53	0.58	0.61	0.78	0.87	0.90	0.89	0.89	0.87
0.6	0.00	0.34	0.49	0.57	0.63	0.67	0.78	0.85	0.87	0.86	0.86	0.85
0.5	0.00	0.34	0.48	0.56	0.61	0.65	0.74	0.80	0.81	0.82	0.82	0.81
0.4	0.00	0.31	0.45	0.52	0.56	0.60	0.69	0.74	0.75	0.76	0.76	0.76
0.3	0.00	0.25	0.37	0.44	0.49	0.52	0.60	0.64	0.66	0.67	0.67	0.68
0.2	0.00	0.19	0.27	0.33	0.36	0.39	0.45	0.49	0.51	0.51	0.51	0.53
0.1	0.00	0.10	0.14	0.17	0.19	0.21	0.25	0.27	0.28	0.29	0.29	0.30

Values of ψ, from Table VIII and Nagaoka's inductance formula. High-frequency Q of a coil of copper wire or thick tubing is given by $Q = 0.15R\psi\sqrt{f}$.

have a diameter less than the mean diameter of the coil and greater than the inner diameter. That is to say, the measured inductance value should lie between the Nagaoka value obtained by using the mean diameter and that obtained by using the inner diameter. This is found to be the case.




Fig. 13. *Variation of optimum ψ with length/diameter.*

Thus, for coil No. 54 (mean diameter 1.72 cm, wire diameter 0.12 cm), the two Nagaoka values corresponding to the inner and mean diameters respectively were 7.8 and 9.0 μH. The measured value was 8.15 μH., and, subtracting a (calculated) lead inductance of 0.13 μH., the coil inductance was 8.0 μH.

The entries in Table IX increase steadily with increasing length/diameter, except that when length/diameter approaches infinity, and $d/s > 0.4$, there is a small decline. This decline seems not to be readily explainable. The last three columns of the ϕ table, it will be remembered, are those resulting from Butterworth's theory when the transverse field term is neglected. The slight anomaly in the ψ table doubtless means that the effect of the transverse field is not quite negligible for length/diameter ratios of 8 and 10, when d/s is greater than 0.4.

The zero Q values for coils of zero length do not mean that the resistance is infinite, but that the inductance has disappeared.

For a given length/diameter, these entries show a rather flat optimum as the spacing ratio varies. In Fig. 12 the optimum spacing ratio is plotted against length/diameter. In Fig. 13 the value of ψ corresponding to the optimum spacing ratio is likewise plotted against length/diameter.

There is an interesting interpretation of ψ analogous to the interpretation of K in Nagaoka's formula. K may be defined as the ratio of the coil inductance to the inductance of an infinitely long cylindrical current sheet having a diameter equal to the mean diameter of the coil. K, in fact, is an end correction. Similarly, it can be shown from the results in reference 13 that ψ is the ratio of the coil Q to the Q at the same frequency of a certain idealized coil. This "coil" is an infinitely long cylinder, having its inner diameter equal to the mean diameter of the coil we are considering and a wall thickness large compared with the current penetration depth, the current being assumed to flow round the inner surface.

14. Low-frequency Resistance of Single-layer Coils.

When we derived a frequency correction to the measured h.f. resistance values, we assumed that the factor we have called k (in the version of Butterworth's formula given in Section 10) was independent of frequency if z was sufficiently high (of the order of 10 or more). This, it was pointed out, is not even approximately true in Butterworth's theory.

Another way of putting this is that, with close spacing of turns, in Butterworth's theory the h.f. resistance does not become proportional to the square root of the frequency until z is very high. When the turns are touching (physically, but not electrically), the h.f. resistance, in the theory, never becomes proportional to $\sqrt{f}$.

Butterworth gives values for his various quantities for z values up to 5, and for infinite z. Table I is based on these latter values. Interpolation for z values between 5 and ∞ is most conveniently done by plotting Butterworth's functions against the reciprocal of z. The values so obtained are, as one might expect, in closer agreement with the experimental results than those of Table I. Thus, when $z = 10$, for length/diameter $= 1$ we have the results of Table X.

TABLE X.

d/s	ϕ	% excess over experimental values
1.0	10.37	87%
0.9	5.57	36%
0.8	3.61	14%
0.7	2.61	6%

In the case of the single coil with $d/s = 0.95$, the theoretical value thus obtained

was about 60 per cent. in excess of the measured value.

Thus, if Butterworth's low-frequency values can be relied upon, his predicted resistances are not so wildly in disagreement with experimental results as appears by comparison of Tables I and VIII, especially since in the top left-hand region of the Table, where the discrepancy will be largest, the coils, for physical reasons, had to be constructed with low z values, between 8 and 10.

We can easily show that these low-frequency Butterworth results are open to considerable suspicion. In fact, we shall see that, in consideration of the degree of approximation tolerated by Butterworth, any agreement with observation must, for closely spaced coils, be regarded as in the nature of an accident.

It was stated in Section 3 that Butterworth worked out each of his three types of loss by solving a set of an infinite number of linear equations, each containing an infinite number of unknowns. He used a method of successive approximations.

Now, when the frequency is low, that is to say, for $z = 5$ or less, the amount of arithmetic involved in proceeding beyond the first approximation becomes very large indeed. Consequently, for these values of z, Butterworth uses the first approximation only.

One can only guess at the error this introduces. For the case of touching wires, when z is infinite, there is an infinite error involved if we take only the first approximation for the transverse field losses. That is to say, the entries in the first row of Table I would be decreased from infinity to a series of not too large finite values.

Whether the converse is true, that is, whether if one proceeded to a sufficiently large number of approximations for the case of touching wires at low frequency an infinite result would be obtained, must be a matter of conjecture. On physical grounds, if a coplanar system of an infinite number of infinitely long touching wires offers infinite impedance to a transverse field of very high frequency, it seems not unreasonable to suppose that it will also offer an infinite impedance to a low-frequency transverse field.

Consequently, for different reasons, the applicability of the Butterworth low-frequency formula to specific coils is open to as much doubt as that of his high-frequency formula.

REFERENCES

[1] S. Butterworth. "Eddy-Current Losses in Cylindrical Conductors, with Special Applications to the Alternating Current Resistances of Short Coils." *Phil. Trans. Roy. Soc.*, 1922, A222, p. 57.

[2] S. Butterworth. "Note on the Alternating Current Resistance of Single Layer Coils." *Phys. Rev.*, 1924, Vol. 23, p. 752.

[3] S. Butterworth. "On the Alternating Current Resistance of Solenoidal Coils." *Proc. Roy. Soc.*, 1925, A107, p. 693.

[4] S. Butterworth. "Effective Resistance of Inductance Coils at Radio Frequencies." *Exp. Wireless & Wireless Engineer*, 1926, Vol. 3, pp. 203, 302, 417 and 483.

[5] S. Butterworth. "Designing Low-Loss Receiving Coils." *Wireless World*, 1926, Vol. 19, pp. 754 and 811.

[6] G. W. O. Howe. "The High-Frequency Resistance of Wires and Coils." *J.I.E.E.*, 1920, Vol. 58, p. 152.

[7] C. N. Hickman. "Alternating-current Resistance and Inductance of Single-layer Coils." Scientific Papers of the Bureau of Standards 1923, Vol. 19, p. 73.

[8] W. Jackson. "Measurements of the High-Frequency Resistance of Single-layer Solenoids." *J.I.E.E.*, 1937, Vol. 80, p. 844.

[9] A. H. Meyerson. "Coil Q Factors at V.H.F." *Communications*, May 1944, p. 36.

[10] W. N. Tuttle. "Bridged-T and Parallel-T Null Circuits for Measurements at Radio Frequencies." *Proc. I.R.E.*, 1940, Vol. 28, p. 23.

[11] D. B. Sinclair. "The Twin-T, A New Type of Null Instrument for Measuring Impedance at Frequencies up to 30 Mc." *Proc. I.R.E.* 1940, Vol. 28, p. 310.

[12] F. E. Terman. "Radio Engineers' Handbook." McGraw-Hill Book Company, 1943.

[13] C. R. Burch & N. R. Davis. "On the Quantitative Theory of Induction Heating." *Phil. Mag.*, 1926, Vol. 1, p. 768.

[14] A. J. Palermo. "Distributed Capacity of Single-layer Coils." *Proc. I..R.E.*, 1934, Vol. 22, p. 897.

[15] J. H. Morecroft. "Resistance and Capacity of Coils at Radio Frequencies." *Proc. I.R.E.*, 1922, Vol. 10, p. 261.

[16] J. C. Hubbard. "On the Effect of Distributed Capacity in Single-layer Solenoids." *Physical Review*, 1917, Vol. 9, p. 529.

[17] G. W. O. Howe. "Calibration of Wave Meters." *Proc. Phys. Soc.*, 1912, Vol. 24, p. 251.

[18] P. H. Massaut. "Distributed Capacitance Chart." *Electronics*, March 1938, Vol. 11, p. 31.

[19] G. W. O. Howe. "On the Capacity of Radio-Telegraphic Antennae." *Electrician*, 1914, Vol. 73, pp. 829, 859, 906.

[20] G. W. O. Howe. "Inaugural Address to the Wireless Section." *J.I.E.E.*, 1922, Vol. 60, p. 67.

Radiocommunication Convention

The Institution of Electrical Engineers is holding a convention, covering the wartime activities in the field of radiocommunications, from 25th to 28th March. The convention will be opened by the President of the Board of Trade, Sir Stafford Cripps, at 5.30 p.m. on Tuesday, 25th March, and he will introduce an address by Colonel Sir Stanley Angwin, on "Telecommunications in War."

On the following days there are to be morning, afternoon and evening sessions at which papers covering naval, military, short and long distance, and pulse communications will be read. Propagation, radio components and future trends will also be covered in the convention.

At a further meeting at 5.30 p.m. on 2nd April there will be a paper on C. W. Navigational Aids.

Physical Society's Exhibition

The 31st Exhibition of Scientific Instruments and Apparatus is being held by the Physical Society on 9th–12th April in the Physics and Chemistry Departments of Imperial College, South Kensington, London, S.W.7.

Admission is by ticket only and is restricted to members of the Society from 10 a.m. to 1 p.m., but it is open to non-members from 2 p.m. to 9 p.m.

CORRESPONDENCE


Letters of technical interest are always welcome. In publishing such communications the Editors do not necessarily endorse any technical or general statements which they may contain.

Q of Solenoid Coils

To the Editor, "Wireless Engineer"

SIR,—From Mr. Medhurst's paper in *Wireless Engineer* for March, one concludes that the results of his careful measurements on solenoid coil Q should be taken as superseding Butterworth's formulæ which have for so long been taken by engineers as a practical basis for coil design.

Mr. Medhurst's results for the Q of coils wound with the optimum gauge of wire are contained in his formula $Q = 0.15R\psi\sqrt{f}$ and his curve for ψ shown in Fig. 13. It is interesting to note that the latter curve agrees to an accuracy of a few per cent with the simple empirical equation $\psi = 1/(1.03 + 0.8R/l)$ as shown in the graph. Thus we arrive



at the following simple and practical formula for the Q of a properly designed solenoid, using plain copper wire, at high radio frequencies :—

$$Q = \frac{\sqrt{f}}{(6.9/R + 5.4/l)}$$

where R and l are the radius and length of the coil in centimetres. In a majority of practical cases we can use the even simpler formula

$$Q = 0.15\sqrt{f}/(1/R + 1/l)$$

which follows the data to a few per cent, provided $l > R$.

The range of conditions under which this formula applies is the same as that to which Mr. Medhurst's data refer : in particular—

(*a*) The ratio of wire diameter to wire spacing must approximate to the optimum (i.e., this ratio should lie between 0.5 and 0.7 for short coils ($l<2R$) or 0.6 to 0.8 for l order of $4R$, and 0.75 to 0.9 for very long coils).

(*b*) The formulæ apply strictly only for very high frequencies, but (from Sect. 10) the accuracy will be better than $\pm$ 10 per cent provided $z>7$; i.e., provided frequency in Mc/s exceeds 0.5 divided by (wire diameter in mm)^2.

Solenoids are chiefly used in current practice on frequencies above about 3 Mc/s, and here Litz wire is of little or no advantage ; the following table, giving the thinnest gauge for which the formula applies to $\pm$ 10 per cent, shows that most practical solenoids will be covered.

freq.	1 Mc/s	4 Mc/s	16 Mc/s
wire ..	22 S.W.G.	28 S.W.G.	37 S.W.G.

(*c*) The formulæ do not hold for coils of very few turns (or extremely short coils). Mr. Medhurst gives us little guidance as to how far Butterworth's correction factor for coils of few turns can be relied on. Further experimental work seems indicated in view of the practical importance of coils of very few turns on v.h.f. and u.h.f.

(*d*) Dielectric loss is not, of course, allowed for. This is unlikely to be material except where the coil has a rather poor dielectric (bakelite or worse) and is used in a circuit having a low parallel tuning capacitance.

M. V. CALLENDAR.

E. K. Cole & Co. Ltd.,
Southend-on-Sea,
Essex.

Absolute Rotation and a Rotating Magnet

To the Editor, "Wireless Engineer"

Sir,—There are two aspects of the old rotating magnet problem : one is the absolute property of rotation, and the other is the electromagnetic reaction on the magnet itself. Various suggestions have been put forward by different authors to explain absolute rotation and from them to interpret the electromagnetic reaction upon the magnet.[1]

The problem is, however, as fundamental as it is hoary. We should especially notice that the questions of absolute acceleration and absolute rotation, which were sanctioned in the special relativity and which signify a return to the Newtonian Hypothesis of absolute space and absolute time, served, in fact, as the genesis of Einstein's theory of general relativity. Einstein's "principle of equivalence" asserts that, for the description of physical processes, we may take either the view-point of an observer A, at rest with an inertial coordinate system or that of another observer B, on a constantly accelerated coordinate system who measures the physical processes by means of the coordinates of observer A and, in addition, assumes the presence of a homogeneous gravitational field.[2] This principle, properly applied here for any particular instant, gives us a simple way of explaining so-called "absolute rotation". The electromagnetic reaction upon a rotating magnet and the resultant electric field distribution in it can then be obtained from Maxwell's equations modified for the relativity effect.

1. *Absolute Rotation*

Consider an inertial system Σ, in which the position-vector of any point is given by

$$\mathbf{r} = \mathbf{i}x + \mathbf{j}y + \mathbf{k}z \quad .. \quad .. \quad .. \quad .. \quad (1)$$

and another coordinate system Σ', with its $\mathbf{k}'$-axis and origin coinciding with the $\mathbf{k}$-axis and origin of the first system, and rotating about the $\mathbf{k}$-axis with constant angular velocity ω. The position-

letter. I did not postulate a " connection " between the propagation difficulties found around 1 cm wavelength and the existence of a limit to the performance of resonator-valves at the same part of the wavelength gamut. On the contrary, I said (Section 10) that it was a " singular coincidence " that two unconnected but fundamental phenomena should both adversely affect radio communication at the same part of the gamut. I am sorry that this does not seem as interesting to Mr. Beck as it does to me, but I am, I fear, unrepentant and still find it well worthy of comment that, at this particular part of the gamut, one finds not merely one but two separate obstacles which have to be taken into account when one is trying to establish communication.

J. H. Owen Harries.

Harries Thermionics Ltd.,
London, W.1.


Q of Solenoid Coils

To The Editor, " Wireless Engineer "

Sir,—Mr. Callendar points out (*Wireless Engineer*, June 1947) that there is little indication in my article as to how far Butterworth's correction factor for coils of few turns can be relied on. That is a deficiency of which I was acutely aware and I can only plead lack of time for making the large number of measurements necessary to fill this gap.

Very tentatively, we can deal with short coils in the following way. Suppose we try to plot curves of ϕ (ratio of h.f. coil resistance to resistance of the same length of straight wire at the same frequency) against the number of turns (n), for various spacing ratios. We know that the curve has to approach asymptotically the values given in column 1 of Table VIII (*Wireless Engineer*, March 1947, p. 88). Also we know two more points, those for $n = 1$ and $n = 2$ values come from Butterworth's exact solution of the problem of two parallel wires carrying high-frequency currents in the same direction (*Proc. Roy. Soc.*, 1925, 107A, p. 708). From these we can draw a plausible looking curve, being guided by the very rough device suggested previously (*Wireless Engineer*, February 1947, p. 39) namely that ϕ should be diminished by $\frac{100}{n}\%$ when n is greater than, say, 20. The results of this procedure are shown in the diagram. Of course, as the ratio of length to diameter increases the curves become modified even for the smaller n values, in what is at the moment, an unpredictable way.

All this juggling with doubtful approximation is clearly quite unsatisfactory, and, as Mr. Callendar



remarks, further experimental work would be useful. It has, however, to be remembered that exact knowledge of the h.f. resistance of coils of two or three turns is likely to be required rather infrequently. The total resistance of circuits containing such coils will usually be dominated by other features of the circuits.

R. G. Medhurst.

G.E.C. Research Laboratories,
Wembley.

WIRELESS PATENTS

A Summary of Recently Accepted Specifications

The following abstracts are prepared, with the permission of the Controller of H.M. Stationery Office, from Specifications obtainable at the Patent Office, 25, Southampton Buildings, London, W.C.2, price 1/- each.

DIRECTIONAL AND NAVIGATIONAL SYSTEMS

581 683.—Amplifier utilizing selective feed-back through a delay network, particularly for the pulsed signals employed in radiolocation.

Standard Telephones and Cables Ltd. and M. M. Levy. Application date 6th June, 1941.

581 696.—Radiolocation system in which the exploring beam covers a conical field of observation in alternately diverging and converging spiral paths.

A. L. Hodgkin. Application date 16th September, 1943.

581 724.—Directive-aerial system including a horn-shaped reflector having two variable earthing points for oscillating the maximum lobe of radiation in order to define an approach path.

Standard Telephones and Cables Ltd. and E. O. Willoughby. Application date 2nd *May*, 1941.

581 762.—Directive aerial comprising a number of forked waveguide dipoles, each provided with spaced apertures, for controlling the relative phasing of the energy-flow inside and outside the guides.

Board of Trustees of the Leland Stanford Junior University. Convention date (U.S.A.) 10th July, 1940.

581 806.—Radiolocation system in which a cathode-